Bruhath Benglauru Mahangara Palike, Dasarhalli Zone
Office of the Executive Engineer, Dasarhalli Division.

Schedule - B

Sl.No	Description of work	Unit	Qty	Rate to be Quoted Jayanma. K	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specifications and directions of engineer in charge of the work	Cum	527.10	172.57	Rupees One Hundred Seventy Two and Fifty Seven Paise Only
2	Removing B S Slab Drain And Stacking etc complete as per specifications and directions of engineer in charge of the work	sqm	677.70	65.72	Rupees Sixty Five and Seventy Two Paise Only
3	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2 complete as per specifications and directions of engineer in charge of the work **From Using Available coarse aggregates**	Cum	59.80	4443.52	Rupees Four Thousand Four Hundred Forty Three and Fifty Two Paise Only
4	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2 complete as per specifications and directions of engineer in charge of the work	Cum	15.50	5159.02	Rupees Five Thousand One Hundred Fifty Nine and Two Paise Only

CONTRACTOR

EXECUTIVE ENGINEER

Scanned by CamScanner

5	Proveding and Laying plain reinforced cement concrete for side drains using M 20 nominul mix concrete with OPC cement 300kgs. With 20mm and down size ganite metal course aggregates @0.69cum and fine aggregates @0.43cum machine mixed,well compacted for walls and bottom including centring,shuttring,cost of materails, HOM of machinaries. Complete Excluding cost of steel asper MORTH Specification no1500,1700,2200. Wall And Bottom thickness 15cm complete as per specifications and directions of engineer in charge of the work	cum	180.72	11032.48	Rupees Eleven Thousand Thirty Two and Forty Eight Paise Only
6	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per pecifications.Specification No. KBS 4.6.3, TMT bars Fe 500. complete as per specifications and directions of engineer in charge of the work	Tonne	10.84	64243.42	Rupees Sixty Four Thousand Two Hundred Forty Three and Forty Two Paise Only
7	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications. and directions of engineer in charge of the work	sqm	373.50	1698.00	Rupees One Thousand Six Hundred Ninety Eight Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division
Bruhath Bengaluru Mahanagara Palike

Scanned by CamScanner